

# FRANK G. FRY PARK EXTENSION

## SCHEDULE OF BID ITEMS

ITEM	APPROXIMATE QUANTITIES	UNIT	ITEMS WITH LUMP SUM OR UNIT WRITTEN IN WORDS	UNIT IN FIGURES	AMOUNT
1.	1	LS	Construction Survey at _____ _____, per lump sum	N/A	\$_____
2.	1	LS	Clearing, Grubbing, Rough Grading and Finish Grade at _____ _____, per lump sum	N/A	\$_____
3.	452	CY	Export and Haul Away at _____ _____, per cubic yard	\$_____	\$_____
4.	1	LS	Landscaped Soil Preparation and Finish Grade at _____ _____, per lump sum	N/A	\$_____
5.	1	LS	Provide Automatic Irrigation System at _____ _____, per lump sum	N/A	\$_____
6.	1	LS	Provide and Install Hydro Seeding at _____ _____, per lump sum	N/A	\$_____
7.	78	EA	Provide and Install 15-Gallon Tree per Plans and Specifications at _____ _____, per each	\$_____	\$_____
8.	5	EA	Provide and Install 24 Inch Box Tree per Plans and Specifications at _____ _____, per each	\$_____	\$_____
9.	1	LS	Provide a 90- Day Maintenance Schedule for Turf and Tree at _____ _____, per lump sum	N/A	\$_____

ITEM	APPROXIMATE QUANTITIES	UNIT	ITEMS WITH LUMP SUM OR UNIT WRITTEN IN WORDS	UNIT IN FIGURES	AMOUNT
10.	162	LF	Provide and Install Low 12 Inch CMU Wall per Plans and Specifications at _____ _____, per lineal foot	\$_____	\$_____
11.	3	EA	Provide and Install Pedestrian Lights per Plans and Specifications at _____ _____, per each	\$_____	\$_____
12.	3	EA	Provide and Install Flood Lights per Plans and Specifications at _____ _____, per each	\$_____	\$_____
13.	2	EA	Provide and Install Collapsible Bollards per Plans and Specifications at _____ _____, per each	\$_____	\$_____
14.	1	LS	Provide and Install Metal Bench, Trash Receptacle, Picnic Table, and Concrete Slab as shown on Plans and per Specifications at _____ _____, per lump sum	N/A	\$_____
15.	5,391	SF	Provide and Install 4 Inch Thick Concrete Paving over Compacted Native per Plans and Specifications at _____ _____, per square foot	\$_____	\$_____
16.	1,645	SF	Provide and Install 6 Inch Thick Concrete Paving over 6 Inch Thick Compacted Base per Plans and Specifications at _____ _____, per square foot	\$_____	\$_____
17.	357	LF	Provide and Install Concrete Header per Plans and Specifications at _____ _____, per lineal foot	\$_____	\$_____

ITEM	APPROXIMATE QUANTITIES	UNIT	ITEMS WITH LUMP SUM OR UNIT WRITTEN IN WORDS	UNIT IN FIGURES	AMOUNT
18.	5,915	SF	Provide and Install Decomposed Granite per Plans and Specifications at _____ _____, per square foot	\$_____	\$_____
19.	1,233	LF	Provide and Install 8 foot High CMU Wall per APWA Standard Plan No. 601-3 at _____ _____, per lineal foot	\$_____	\$_____
20.	341	CY	Provide and Install Class 2 Aggregated Base under Turf per Plans and Specifications at _____ _____, per cubic yard	\$_____	\$_____
21.	1	LS	Provide and Install Metal Vehicle Barrier (Swing Gate) and 6" Pipe Bollard per Plans and Specifications at _____ _____, per lump sum	N/A	\$_____

**TOTAL OR GROSS SUM BID**

**TOTAL IN FIGURES:**

\$\_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**(Written in Words):**

**(Written in Figures):**

### **ALTERNATE BID ITEM**

1.	946	LF	Remove the Existing Fence, Provide and Install 6 foot High Galvanized Chain Link Fence per Plans and Specifications at _____ _____, per lineal foot	\$_____	\$_____
----	-----	----	---	---------	---------